



## Hopi Jr & Sr High School Temporary Water System *Design Build*

FE served as the Design Builder on this project providing a temporary water system to by-pass the existing elevated storage tank, which needed to be removed from service and repaired. Included with the installation were three 10,000-gallon storage tanks and two booster pumps equipped with variable frequency drives to maintain a steady pressure under variable demands, including fire protection.

**Owner:** Hopi Jr/Sr High School  
**Role:** Design Builder  
**Contract Amount:** \$76,030  
**Final Contract Amount:** \$76,030  
**Project Start Date:** March 2009  
**Project Completion Date:** Aug 2009

**Fann Environmental Key Personnel:**

Mike Young - Project Manager  
Jeff Sawyer - Project Estimator  
Mark Clevenger - Supervisor



**References:**

Garlyn Navakuku, Facilities Manager, 928-738-5111 ext 242